PBS INSTRUCTION 100-20 BREB INSTRUCTION 500-07

ENERGIZATION AND COMMISSIONING OF ELECTRIC NETWORK SYSTEM (ELECTRIC LINES OR LINE SECTION AND SUB-STATION)

BANGLADESH RURAL ELECTRIFICATION BOARD PBS INSTRUCTION 100-20/ BREB INSTRUCTION 500-07

Approval Date: 07/03/1979 Revision Date: 19/02/2020

SUBJECT: ENERGIZATION AND COMMISSIONING OF ELECTRIC NETWORK
SYSTEM (ELECTRIC LINES OR LINE SECTION
AND SUB-STATION)

I. PURPOSE

To establish and set forth BREB policy procedure with respect to the energization and the commissioning of electric network system and the required approvals and notifications prerequisite to the energization.

II. GENERAL

The energization of electric network system is for the purpose of connecting the system to its source of power and testing the equipment and construction for satisfactory performance. Commissioning of the system is the act of turning the system over to the PBS for operation and service to its consumer members.

III. POLICY AND PROCEDURE

A. In order to provide electric service to members and other consumers at the earliest possible date and to assist in the elimination of conductor theft, it shall be the policy of BREB and PBS to energize electric lines or line sections as soon as they are ready for service.

	BANGLADESH	RURAL ELECTRIFI	CATION BOARD	
	PBS Instructio	on 100-20/ BREB Inst	ruction 500-07:	
ENERGIZATI	ON AND COMM	ISSIONING OF ELE	CTRIC DISTRIBUT	TON SYSTEM.
Date of Origin	Revised by	Approved by	Page No.	Revision No.
07/03/1979	BREB	BREB Board	Page 1 of 25	4
		BREB Board 996, 01/09/2013 & 1		4

(Md Mozibur Rahman) Md. Duhidul Islam) Consultant, TAPP, BRBBSuitant, TAPP BREF (Md. Mdzaminei Huq) Consultant, TAPP, BREB

(Md. Abdul Khaleque)
Consultant TAPP RREP

(Md. Ahsanul Hague) Consultant, TAPP, BREB (Debasish Chakrabortty) PD, TAPP, BREB ৬২১ তম বোর্ড সভায় অনুমোদিত সিদ্ধান্ত নং ১৭৭০০

(Kamful Ahsan Mollik) Asst. Secy. (Board), BRER

B. Final Joint Inspection

Before energization of sub-station and electric lines, the Contractor will request or final inspection of the sub-station/electric lines along with a free hand single line diagram of the line section to be energized and duly filling up 5 (five) copies of BREB Form No. 459 (Notice of Electric Sub-Station/ Line Energization Form). On receiving the request of final inspection the consultant will thoroughly check sub-station/electric lines and will identify deviations if any and will notify the contractor to rectify those deviations within stipulated time of 7(seven) days or less. After rectification the contractor will notify the consultant that the deviations have been rectified and the sub-station/electric lines are now ready for final inspection. The Consultant will forward this notification to the AE of BREB or AGM(E&C)/AGM(O&M)/DGM(Tech-HQ) of PBS to organize joint (final) inspection. In case of construction is being carried out by BREB, AE of BREB will fix up a date for joint (final) inspection and inform the contractor, consultant and PBS. In case of construction is being carried out by PBS, AGM(E&C)/AGM(O&M)/DGM(Tech-HQ) of PBS will fix up a date for joint (final) inspection and inform the contractor and consultant.

The joint inspection will be conducted by the following persons.

- (a) Representative of BREB (For Sub-station AE, for electric line AE or his/her representative)
- (b) Representative of PBS, AGM (E&C)/ AGM(O&M) or selected by him/ her (not below the rank of AJE).
- (c) Consultant's Engineer (not below the rank of Junior Engineer)

	BANGLADESH	RURAL ELECTRIFI	CATION BOARD	
-	PBS Instructio	n 100-20/ BREB Inst	ruction 500-07:	
ENERGIZATI	ON AND COMM	ISSIONING OF ELE	CTRIC DISTRIBUT	TON SYSTEM.
Date of Origin	Revised by	Approved by	Page No.	Revision No
07/03/1979	BREB	BREB Board	Page 2 of 25	4
Revision Date: 31	/04/1995, 14/11/1	996, 01/09/2013 & 1	9/02/2020	

(Mc Voznour Rahman)
Consultant TAPP BREP

(Md. Duhidul Islam, Consultant, TAPP, BRE (Md. Mozammei Huq) Consultant, TAPP, BREP

(Md. Abdul Khaleque)

(Md. Ahsanul Haque) Consultant TAPP, BREB (Debasish Chakrabortty) PD, TAPP, BREB ১১ তম বোর্ড সভায় অনুমোদিত সিদ্ধান্ত নং ১৭৭০

Act See (Beach Door

(d) Contractor's Supervisor/ Representative.

In case of construction by PBS, representative of BREB may not be required to attend.

During the final joint inspection As Built Staking Sheet will be verified for its

correctness. If the final joint inspection finds the system satisfactory then, the representatives will sign the As-Built Staking Sheets as endorsement of acceptance.

C. Energization

In order to establish the responsibility for the electric lines operation with the PBS, the 5 (five) copies of Notification of Electrical Sub-station/ Line Energization BREB Form No.459 will be forwarded to the Executive Engineer or Sr. GM/ GM by the Consultant. In case the construction is being carried out by BREB, the Executive Engineer will approve the Energization Notice and post his/ her records of electric lines to be turned over to the PBS for operation and forward 2 copies to the AGM(O&M), 1 copy to Consultant & 1 copy to Contractor 7 (seven) days ahead of Energization date. In case the construction is being carried out by PBS, the Senior General Manager/ General Manager will approve the Energization Notice and post his/ her records of electric lines for operation and forward 2 copies to the AGM(O&M), 1 copy to Consultant & 1 copy to Contractor 7 (seven) days ahead of Energization date.

The AGM(O&M) of PBS will fix a date for energization. If an interruption of service to an electric line that will feed the new line section is required, then the **Notice** should be accompanied by the necessary "Request for Outage" (BREB Form No. 458). Upon receipt of the Notice of Electrical Line Energization, the AGM(O&M) will make a physical inspection of the electric line and line equipment, familiarize him/

	BANGLADESH .	RURAL ELECTRIFI	CATION BOARD	
	PBS Instruction	n 100-20/ BREB Inst	ruction 500-07:	
ENERGIZATI	ON AND COMM	ISSIONING OF ELE	CTRIC DISTRIBUT	ION SYSTEM.
Date of Origin	Revised by	Approved by	Page No.	Revision No
07/03/1979	BREB	BREB Board	Page 3 of 25	4
Revision Date: 31	/04/1995 14/11/1	996 01/09/2013 & 1	9/02/2020	

(Md. Mozibur Rahman)

(Md. Duhidul Islam)

Md. Mozammer Huq) consultant, TAPP, BREP (Md. Abdul Khaleque) Consultant, TAPP, BREB

(Debasish Charabortty)

৬২১ তম বোর্ড স<mark>ভায় অনুমোদিত</mark> সিদ্ধান্ত নং ১৭৭<mark>০০</mark>

(Kamrul Ahsan Mollik) Asst. Secy. (Board), BRUD herself with the customers to be served, schedule meter sets and service connections, and post his/ her operating maps and records as to the electrical line in service. Posting of information in the operating maps must be completed within seven (7) days.

- Energization of Sub-stations and electric lines will be done by the PBS's personnel under the direction and supervision of the PBS's engineer, Consultant, the BREB officials and Contractor or other authorized officer.
- Only those employees of the PBS, who have been successfully trained to energize RE system will be permitted to participate in the energization.
- Distribution transformers shall remain disconnected from the primary HV conductor.
- Approved Engineers of BREB to act as Government Electrical Inspectors must be notified in advance of energization to permit them to make an inspection of the system before energization.
- 5. A notice must be placed either in the press in the area, where energization of electric lines is to take place notifying the public of that fact or the public may also be notified by local announcement.
- The system shall be energized in segments, beginning with the sub-station and continuing from sectionalizing point to sectionalizing point working outward from the sub-station.
- Switches and sectionalizing devices shall be operated to ensure their satisfactory operation.
- Particular attention should be given to junctions and taps from the primary line to observe see that all connections have been properly made in the system neutral.
- No electric line shall be energized until it is totally complete including LT underbuild. Daily interruptions after energization is not desirable. For backbone

	BANGI ADESH	RURAL ELECTRIFI	CATION BOARD	
		n 100-20/ BREB Inst		
ENERGIZATI		ISSIONING OF ELE		TON SYSTEM.
Date of Origin	Revised by	Approved by	Page No.	Revision No
07/03/1979	BREB	BREB Board	Page 4 of 25	4
120.00.00.00.00.00.00.00.00.00.00.00		BREB Board 996, 01/09/2013 & 1		4

Md Mozibur Rahman) Onsultant TAPP BRER

(Md. Duhidul Islam) Consultant TAPP BRE (Md. Mozammel Huq)

(Md. Abdul Khaleque)

২২১ তম বোর্ড সভায় অনুমোদিত সিদ্ধান্ত নং ১৭৭০

Md. Ahsanul Haque)

(Debasish Charraborth)
PD, TAPP, BREB

(Kamui Alean Mothe) Asst. Secy. (Board), BRER electrical lines may be partly energized for the safety of the conductors. In case of energization of other three phase lines, the section shall be between two sectionalizing points or between HT dead ends those are a part of the original line design. HT and LT laterals from the line section need not be completed prior to the energization of the line section. Single phase lines will normally be energized only after the entire line is completed, complete with LT under build and transformer installations.

The only exception to this will be where the extreme end of the electric line cannot be completed for an extended period of time because of high water, shortage of materials and construction obstacle. It shall be assumed that all LT lines and laterals served by the HT line being energized will also be energized at the same time or not later than one week after the HT line is energized and that the LT lines can be safely energized without interrupting service to the HT line which serves it.

10. Formal energization of sub-station shall be made by using BREB Form No. 459, after performing necessary testing and commissioning works. Before formal energization, prescribed form of testing and commissioning will have to be filled up with the signatures by the members of standing committee of sub-station testing and commissioning. Sub-station testing and commissioning shall be carried out in accordance with the procedure laid down in Sub-station Testing and Commissioning section of PBS Instruction 100-29. Filled up form of Sub-station testing and Commissioning shall be a part of BREB Form No. 459 for energization a Sub-Station.

-	BANGLADESH	RURAL ELECTRIFIC	CATION BOARD	
	PBS Instructio	n 100-20/ BREB Inst	ruction 500-07:	
ENERGIZATI	ON AND COMM	ISSIONING OF ELEC	CTRIC DISTRIBUT	ION SYSTEM.
Date of Origin	Revised by	Approved by	Page No.	Revision No
07/03/1979	BREB	BREB Board	Page 5 of 25	4
Revision Date: 31	/04/1995, 14/11/1	996, 01/09/2013 & 19	9/02/2020	

(M. Mokum Rahman) Consultant, TAPP, BREB Onsultant TAPP BREE

(Mu. Nozammer may, Consultant, TAPP, BREI

(Md. Abdul Khaleque)

(Md. Ahsanul Hague) Consultant TAPP, BREB (Debasish Chakrabortty) PD,TAPP, BREB

৬২১ তম বোর্ড সভায় অনুমোদিত সিদ্ধান্ত নং ১৭৭০০

(Illimming and Moline) Asst. Secy. (Board), BREB.

- 11. Before energization a sub-station and electric lines the followings must be completed:
 - (a) Joint Inspection;
 - (b) Right of Way clearing;
 - (c) Joints and connections are properly made;
 - (d) Public notification by Newspaper/local announcement;
 - (e) Distribution transformers are isolated from electrical lines.
 - (f) Energization is programmed to charge electric line sections progressively from source end.
 - (g) Programmed charging of Distribution Transformers when consumers complete their house wiring.
 - (h) Transformer Record Card is filled in and updated electronically.
 - (i) Testing and commissioning form is filled up for sub-station.

VI. SUBSTATION TESTING & COMMISSIONING

A. General

There are two sets of forms designed for the purpose of sub-station testing and commissioning. These forms are to be filled out prior to commercial commissioning and energization of Sub-station. All construction works of the Sub-station are to be completed before testing and commissioning.

The two sets of testing and commissioning forms enclosed herewith as follows-

- (a) Sub-station Testing and Commissioning Form No. 100-20-01 (7 pages) must be filled out for both Outdoor and Indoor type Sub-station prior to commercial commissioning and energization;
- (b) Sub-station Testing and Pre-Commissioning Form No. 100-20-02 (6 pages) must be filled out along with Form No. 100-20-01 only for Indoor type Sub-station prior to commercial commissioning and energization;

	BANGLADESH	RURAL ELECTRIFI	CATION BOARD	
	PBS Instructio	n 100-20/BREB Inst	ruction 500-07:	
ENERGIZATI	ON AND COMMI	ISSIONING OF ELE	CTRIC DISTRIBUT	ION SYSTEM.
Date of Origin	Revised by	Approved by	Page No.	Revision No.
07/03/1979	BREB	BREB Board	Page 6 of 25	4

(Md Mozibur Rahman) Consultant TAPP BREP

(Md Duhidul Islam)

(Md. Mozamme) Huy, Consultant, TAPP, BRE (Md. Abdul Khaleque) consultant TAPP BREB

(Md. Ahsanul Haque) onsultant TAPP BREE

(Debasish Chakrabortty)
PD, TAPP, BREB

৬২১ তম বোর্ড সভায় <mark>অনুমোদিত সিদ্ধান্ত নং ১৭</mark>৭০০

(Kamrul Ahsan Mollik)
Asst. Secy. (Board), BREB.

B. Guidelines

Where test result data is required, Sub-station Construction Division of BBEB will be designated to carry out the testing. It is the responsibility of the Executive Engineer of the said Sub-station Construction Division to ensure that the testing is done as per professional and approved methods. He/ She or his/ her representative (not below the rank of Assistant Engineer) will sign the form at the time of testing. Where two signatures are required, the Executive Engineer of Sub-station Construction Division and his/ her most immediate subordinate will sign the form.

During pre-commissioning stage of indoor type sub-station, computer generated Testing and Pre-Commissioning Form 100-20-02 (6 pages) shall be used in presence of a technical team. All members of this technical team shall witness the Precommissioning Report. The Technical Team shall be consisted as follows-

- (a) AE of Sub-station construction division, BREB
- (b) AGM(E&C) of concerned PBS
- (c) One Technical Representative from Contractor
- (d) One Technical Representative from Consultant

All data entries will be done in BLOCK LETTERS.

All equipment nomenclature will be entered on the form before the substation is scheduled for commissioning.

All required Insulation and Continuity Tests will be performed before the permanent leads are connected. The equipment will be tested before the final connection is made. This will eliminate the need to remove the leads at a later date for retesting.

All required Oil Dielectric Test samples will be made and all results recorded before the substation is scheduled for commissioning.

All Mechanical/ Electrical Tests and Inspection Results will be completed before the Sub-station is scheduled for commissioning.

Upon completion of Testing and Commissioning, the equipment installation and operation manuals will be handed over to the PBS. Sub-station Testing, Commissioning and initial energization shall be completed by a standing committee. The committee will be formed as follows-

(a) Representative of Sub-station Construction Division of BREB (Not below the

	BANGLADESH	RURAL ELECTRIFI	CATION BOARD	
	PBS Instructio	n 100-20/ BREB Inst	ruction 500-07:	
ENERGIZATI	ON AND COMMI	ISSIONING OF ELE	CTRIC DISTRIBUT	
Date of Origin	Revised by	Approved by	Page No.	Revision No
07/03/1979	BREB	BREB Board	Page 7 of 25	4
Revision Date: 31	/04/1995, 14/11/19	996, 01/09/2013 & 1	9/02/2020	

5 (Md Duhidul Islam) OIL TAPP BREI

onsultant, TAPP, BREB

ivia, ivioxammer riugi

APP, BREB (Md. Abdul Khaleque)

৬২১ তম বোর্ড স**ভায় অনুমোদিত সিদ্ধা**ন্ত নং ১৭৭০০

(Kamrul Ahsan Mollik)

(Md. Ahsamul Haque) (Debasish Chakrabo Consultant, TAPP, BREB PD, TAPP, BREB

Asst. Secy. (Board), BREB.

rank of Assistant Engineer)

- (b) Technical Representative of PBS(Not below the rank of AGM)
- (c) Representative of Contractor
- (d) Representative of Consultant

CAUTION

OBSERVE ALL PRECAUTIONS- THERE IS INCREASED RISK TO DANGER ON INITIAL EQUIPMENT ENERGIZATIONS. EQUIPMENT OPERATIONS ONLY BE PERMITTED WITHIN THE FENCED AREA UPON INITIAL ENERGIZATION.

	BANGLADESH	RURAL ELECTRIFI	CATION BOARD	
		n 100-20/ BREB Inst		
ENERGIZATI	ON AND COMM	ISSIONING OF ELE	CTRIC DISTRIBUT	
Date of Origin	Revised by	Approved by	Page No.	Revision No.
07/03/1979	BREB	BREB Board	Page 8 of 25	4
Revision Date: 31	/04/1995, 14/11/1	996, 01/09/2013 & 1	9/02/2020	

(Mo Mozibur Rahman) Consultant TAPP, BREB (Md. Duhidul Islam) Consultant, TAPP, BREP (Md. Mozamme) Huq) Consultant, TAPP, BREP (Md. Abdul Khaleque) Consultant, TAPP, BREB

(Md. Ahsanul Haque) Consultant, TAPP, BREB (Debasish Chakrabortty)
PD, TAPP, BREB

৬২১ তম বোর্ড সভায় অনুমোদিত সিদ্ধান্ত নং ১৭৭০০

(Kamrul Ahsan Moltita). Asst. Secy. (Board), BREB.

BANGLADESH RURAL B BREB Form No. 100-20-01(Version-1)	CLECTRIFICATION BOARD (Page- 1 of 7)
	& COMMISSIONING FORM
PBS:	Sub-Station Name:
Capacity (MVA	- ID No.:
Length of 33 Source Line: Km	Date of Commissioning:

Name of Source Grid: ---A. SUBSTATION EQUIPMENT DATA AND READINGS (1) POWER TRANSFORMERS

Transformer Type	Three Phase Single		Single l	Phase		
Location	X-er: 1	X-er: 2	R	Y	В	Spare
1. Serial No.						
2. Manufacturer						
3. Winding Temp (°C)						
4. Liquid Temp (⁰ C)						-
5. Pressure(PSI/MPA)						
6. Liquid Level						

(2) ACR/OCR/BREAKER

Location	33 KV			11 KV I	Peeder		
Particulars		1A	2B	3C	4D	5E	6F
Type (ACR/OCR/Breaker)							
Serial Number					West of the last o		
Manufacturer							
Rating (Amps)							
Counter Reading						1	
Oil Level		1 10					
Remarks							

	BANGLADESH I	RURAL ELECTRIFI	CATION BOARD	
	PBS Instructio	n 100-20/ BREB Inst	ruction 500-07:	
ENERGIZATI	ON AND COMMI	SSIONING OF ELE		TON SYSTEM.
Date of Origin	Revised by	Approved by	Page No.	Revision No.
07/03/1979	BREB	BREB Board	Page 9 of 25	4
Revision Date: 31	/04/1995, 14/11/19	996, 01/09/2013 & 1	9/02/2020	

(Md. Mozibur Rahman) Consultant TAPP BREE

(Md. Ansanul Haque) Consultant, TAPP, BREB

(Md. Duhidul Islam) Consultant, TAPP BREI

(Debasish Chakrabo(tty)

PD, TAPP, BREB

(Md. Mozammel Huq) Consultain/localinininining/Flub)

(Md. Abdul Khaleque) Consultant TAPP, BREB

৬২১ তম বোর্ড সভায় অনুমোদিত সিদ্ধার নং ১৭৭০০

(Kamrul Ahsan Mollik) Asst. Secy. (Board), BREB. (3) VOLTAGE REGULATORS

(Page- 2 of /7)

Phase	Name of Manufacturer	Serial No.	Rating (A)	Counter Reading	Oil Level	SETTINGS:- Time Delay:
R						Bandwidth:
Y						Voltage:
В						Resistance:

(4) METERING AND PANEL	
Type of Meter:	Meter Serial No.:
Meter Reading while energizing:	KWH
CT Ratio while energizing:	PT Ration while energizing:
Multiplying Factor: (In Word	

SL No.	Particulars	Reading	Remarks
1	KWHD		V
2	KVARHD		
3	Instantaneous KWD		*
4	Instantaneous KVARD		
5	Instantaneous KVA		
6	Instantaneous KV (A)		
7	Instantaneous KV (C)		
8	Instantaneous PF		
9	Max KWD		- X
10	Max. KVA	22	
11	PWD		
12	Instantaneous KV (A)		
13	Instantaneous KV (C)		
14	SAS (Sub-station Automatic System)		
15	CRP (Control Relay Panel)		

1. Reading Taken by any member of the Standing Committee (Name & Designation with Seal & Signature):

2. Reading Witnessed by other members of the Standing Committee (Name & Designation with Seal & Signature):

	BANGLADESH I	RURAL ELECTRIFI	CATION BOARD	
		n 100-20/ BREB Inst		
ENERGIZATI	ON AND COMMI	SSIONING OF ELE	CTRIC DISTRIBUT	ION SYSTEM.
Date of Origin	Revised by	Approved by	Page No.	Revision No.
07/03/1979	BREB	BREB Board	Page 10 of 25	4
Revision Date: 31	/04/1995, 14/11/19	996, 01/09/2013 & 1	9/02/2020	

(Md Mozibur Rahman) Consultant TAPP BREP

(Md. Duhidul Islam) (Md. Mozammet Hug) Consultant, TAPP BRE Consultant, TAPP BREP

(Md. Abdul Khaleque)

৬২১ তম বোর্ড সভায় অনুমোদিত সিদ্ধান্ত নং ১৭৭০০

ebasish Chaki portty, PD, TAPP, BREB. (Debasish Chak (Md. Ahsanul Haque) Consultant, TAPP, BREB

(Kamrul Ahsan Mollita) Asst. Secy. (Board), BREB.

(Page- 3 of 7)

B. OIL DIELECTRIC STRENGTH TEST RESULTS (KV) OF EQUIPMENT

(1) POWER TRANSFORMERS

Туре	Location	Manufacturer	Serial No.	Job No.	Test Date	Test Result
3-Ø	Transformer-1					
3-10	Transformer-2					
	No. 1 (R)					
1.0	No. 2 (Y)			4		
1-Ø	No. 3 (B)					
	No. 4 (Spare)	ři.				
Statio	n Transformer					

(2) VOLTAGE REGULATORS

Phase	Manufacturer	Serial No.	Job No.	Test Date	Test Result
Red					
Yellow					
Blue					

(3) ACR/ OCR/ VCB/ BREAKER (NOTE: Test in Open Position (Yellow Handle down)

Location	Manufacturer	Serial No.	Job No.	Test Date	Test Result
1.33KV Incoming					
2. 11KV Feeder '1A'					
3. 11KV Feeder '2B'			2-		
4. 11KV Feeder '3C'					
5 11KV Feeder '4D'					
6. 11KV Feeder '5E'					
7. 11KV Feeder '6F'				8	

1. Tests Performed by any member of Standing Committee (Name & Designation with Seal & Signature):

2. Tests Witnessed by other members of Standing (Name & Designation with Seal & Signature):

	BANGLADESH 1	RURAL ELECTRIFI	CATION BOARD	
		n 100-20/ BREB Inst		
ENERGIZATI	ON AND COMM	SSIONING OF ELE	CTRIC DISTRIBUT	ION SYSTEM.
Date of Origin	Revised by	Approved by	Page No.	Revision No.
07/03/1979	BREB	BREB Board	Page 11 of 25	4
Revision Date: 31	/04/1995, 14/11/19	996, 01/09/2013 & 1	9/02/2020	

Consultant, TAPP, BREB

(Md Duhidul Islam) Consultant TAPP BREI (Md. Mozammei Huq) Consultant, TAPP, BREF (Md. Abdul Khaleque)
Consultant TAPP RREB

(Md. Ahsanul Haque, Consultant, TAPP, BREB

(Debasish Charrabortty)
PD,TAPP, REB

८२) जन त्याच मधांत्र अमूर्साम्य मिकाळ नेर १११००

(Kamrul Ansan Molhik)

C. INSULATION AND CONTINUITY TEST RESULTS (RESULTS IN MEGAOHMS)

Location	Manufacturer	SL. No.	HT-Grd	LT-Grd	H1-H2-H3	X1-X2-X3
X-er1						
X-er2						
R	A-2					
Y						
В						
S					21	
	X-er1	X-er1	X-er1		X-er1	X-er1

Phase	Manufacturer	Serial No.	S-GRD	L-GRD	SL-GRD	SL-L	SL-S	S-L
Red				77				
Yellow								
Blue								

(3) ACR/ OCR/ VCB/ BREAKER (RESULTS IN MEGAOHM) NOTE: TEST IN OPEN POSITION (YELLOW HANDLE DOWN)

Location	Source-Grd		Lo	Load-Grd		Source		Load				
A.	R	Y	В	R	Y	В	R-Y	Y-B	B-R	R-Y	Y-B	B-R
33KV Incoming							8					
11KV Feeder '1A'												
11KV Feeder '2B'												
11KV Feeder '3C'												
11KV Feeder '4D'												
11KV Feeder '5E'												
11KV Feeder '6F'	l ly											

	BANGLADESH	RURAL ELECTRIFI	CATION BOARD	
		n 100-20/ BREB Inst		
ENERGIZATI			CTRIC DISTRIBUT	ION SYSTEM.
Date of Origin	Revised by	Approved by	Page No.	Revision No.
07/03/1979	BREB	BREB Board	Page 12 of 25	4
Revision Date: 31	/04/1995, 14/11/1	996, 01/09/2013 & 1	9/02/2020	

(Md. Meribur Rahman)
Consultant TAPP BREP
Consultant TAPP BREP

(Md. Mozammer Huq) Consultant, TAPP, BREP

(Md. Abdul Khaleque)

(Md. Ansanul Haque) Consultant, TAPP, BREB

(Debasish Chakr bortty) PD, TAPP, BREB

৬২১ এন বোর্ড সভায় অনুমোদিত সিদ্ধান্ত নং ১৭৭০০

(Kamrul Ahsan Mollik) Asst. Secv. (Board) DDER (4) LIGHTNING ARRESTERS (RESULTS IN MEGAOHMS)

Location	R- F	Phase	B-F	hase	Y- Phase		Sı	oare
	SL No.	Reading	SL No.	Reading	SL No.	Reading	SL No.	Reading
33KV Incoming						22		
Power X-er HT								
Power X-er LT								
11KV Feeder '1A'								
11KV Feeder '2B'								
11KV Feeder '3C'			10					
11KV Feeder '4D'								
11KV Feeder '5E'								
11KV Feeder '6F'								

(5) INSTRUMENT TRANSFORMERS (RESULTS IN MEGAOHMS)

Equipment	Phase	Manufacturer	SL No.	HT-GRD	LT-GRD	H1-H2	HT-LT
CT	R						
CT	Y						
CT	В						
PT	R						
PT	Y						
PT	В						

(6) GROUND RESISTANCE TEST RESULTS (RESULTS IN OHM)

SL No.	Distance of Test Probe #1 From Instrument (M)	Distance of Test Probe #2 From Instrument (M)	Resistance of Ground Grid to Earth (Ohms)	Average Reading (Ohm)
1	TV.			
2			я.	

1. Tests Performed by any member of Standing Committee (Name & Designation with Seal & Signature):

2. Tests Witnessed by other members of Standing (Name & Designation with Seal & Signature):

	BANGLADESH	RURAL ELECTRIFI	ICATION BOARD	
10	PBS Instructio	n 100-20/ BREB Inst	truction 500-07:	
ENERGIZATI			CTRIC DISTRIBUT	ION SYSTEM.
Date of Origin	Revised by	Approved by	Page No.	Revision No
07/03/1979	BREB	BREB Board	Page 13 of 25	4
Revision Date: 31	/04/1995, 14/11/1	996, 01/09/2013 & 1	9/02/2020	

(Md. Mozibur Rahman) Consultant TAPP, BREB

(Md. Duhidul Islam) Consultant TAPP BRET

(Md. M. zammei Huq) Consultant, TAPP, BREF

(Md. Abduf Khaleque) Consultant TAPP BRER

(Md. Ahsanul Haque) Consultant, TAPP, BREB



(Kamrul Ahsan Mothik) Asst. Serv (Poo-

D. MECHANICAL TESTS AND OVER ALL INSPECTION RESULTS

SL No.	Items	Result (OK/ Not OK)	Name, Designation & Office/ Organization	Signature
1	Equipment Lead Connections Tightness			
2	Bus Assembly and Connections (33 KV & 11 KV)			
3	33 KV Air Break Switch Alignment and Adjustment (Switch No. 199)			
4	11 KV Air Break Switch Alignment and Adjustment (Switch No. 166).			
5	11 KV Feeder Disconnect Switches Alignment and Adjustment			
6	Conduit Installation and Connections			
7	Equipment & Yard Ground Connections		8	
8	Yard Civil Works and Finishing		×	
9	Control Building Construction (if any)			
10	Security Post, Guard Room Construction			
11	Foundation of Control Building and Equipment Pad			1
12	Boundary Wall, Fence, Gate Installation	N A	20	
13	Steel structure Erection Inspection			

 Tests Performed by any member of Standing Committee (Name & Designation with Seal & Signature):

2. Tests Witnessed by other members of Standing (Name & Designation with Seal & Signature):

	BANGLADESH	RURAL ELECTRIFI	CATION BOARD	
	PBS Instructio	n 100-20/ BREB Inst	truction 500-07:	
ENERGIZATI	ON AND COMM	ISSIONING OF ELE	CTRIC DISTRIBUT	ION SYSTEM.
Date of Origin	Revised by	Approved by	Page No.	Revision No
07/03/1979	BREB	BREB Board	Page 14 of 25	4
Revision Date: 31	/04/1995, 14/11/1	996, 01/09/2013 & 1	9/02/2020	

(Md. Mozibur Rahman) (Md. Duhidul Islam)
Consultant TAPP BREPCOnsultant TAPP BREP

(Debasish Chakrabortty)
PD TAPP, BREB.

(Md. Nozammel Hug) Consultant, TAPP BREI (Md. Abdul Khaleque) Consultant TAPP BREB

৬২১ তম বোর্ড সভায় **অনুমোদিত সিদ্ধান্ত নং ১৭**৭০০

(Kamral Ahsan Molfik)
Asst Secv (Roard) Barr

(Md. Ahsanul Haque)

DECLARATION

We the undersigned checked the above mentioned works and equipment, verified test data and found the results satisfactory on today ------ 20----. This outdoor/ indoor type substation is ready for energization and fit for commercial operation.

SL No.	Name	Designation & Office/ Organization	Signature
1	H.S. M.	w v	
2	FT T		
3	M		
4			
5			
6			8
7	7,50		· · · · · · · · · · · · · · · · · · ·
8			
9			
10			
11			
12			1
13			
14			

		RURAL ELECTRIFI		
,		n 100-20/ BREB Inst		
ENERGIZATI	ON AND COMMI	ISSIONING OF ELE	CTRIC DISTRIBUT	
Date of Origin	Revised by	Approved by	Page No.	Revision No.
07/03/1979	BREB	BREB Board	Page 15 of 25	4
Revision Date: 31	/04/1995, 14/11/19	996, 01/09/2013 & 1	9/02/2020	

(Md. Mozibur Rahman)

(Md. Dunidul Islam) Consultant, TAPP BREF (Md. Mozammei Huq) Consultant, TAPP, BREF (Md. Abdul Khaleque) Consultant, TAPP, BREB

(Md. Ahsanul Haque) Consultant, TAPP, HREB

(Debasish Chakrabortty) PD, TAPP, BREB.

৬২১ তম বোর্ড সভায় অনুমোদিত সিদ্ধান্ত নং ১৭৭০০

(Kamrul Ansan Moline)
Asst. Secy. (Board), BRER

BREB Form No. 100-20-02 (Version-1)

(Page- 1of 7)

PBS: Sub	o-Station Name:
Capacity (MVA	
Length of 33 Source Line: Km	Date of Commissioning:

SL No.	Item No.	Description of Items	Completion Status (OK/ Not OK/ Not Done)	Remarks
01		DESIGN SERVICES		
(a)		All design & drawings for specific site sub-station		
(b)		All other documentation works like 5 (five) sets of As-Built Drawings, Cable schedule Drawing, Sub- station Operation and Maintenance Manual etc.		
02		ELECTRICAL		
(a)		All switchyard Mechanical and Electrical Equipment (Power Transformer, Station Transformer, Breaker, CT/PT, etc.) installation including cables Termination to Control Building.		
(b)		33 KV RTCC & Transformer Panel Installation in Control Room with all accessories and cable terminations		
(c)		11 KV Switchgear Panel Incomer Panel, Bus coupler Installation in Control Room with all accessories and cable terminations.		
(d)		Battery, Battery Charger & AC-DC Distributional Panel Installation, AC Panel to MDB connection in Control Room with all accessories and cable terminations.		

	BANGLADESH	RURAL ELECTRIFI	CATION BOARD	
ENEDGIZATI		n 100-20/ BREB Inst	ruction 500-07: CTRIC DISTRIBUT	ION SYSTEM
Date of Origin	Revised by	Approved by	Page No.	Revision No
07/03/1979	BREB	BREB Board	Page 16 of 25	4

(Md. Mozibur Rahman) Consultant TAPP BREP

(Md. Duhldul Islam) Consultant TAPP BREP

(Md. Nozammei Huq, Consultant, TAPP BREI

(Md. Abdul Khaleque)
onsultant TAPP, BREB
৬২১ তম বোর্ড সভায় অনুমোদিত সিদ্ধান্ত নং ১৭৭০০

(Md. Ahsanul Haque)

(Debasish Chakrabortty) PD, TAPP, EREB.

(Kamrul Ansan Mollik) Asst. Secy. (Board), BREB.

Page-2 of 7

Installation of Neutral cable, Outside Industrial	101
Socket all out going feeders and other cables	
etc.	
Supply and Installation of Sub-station Lighting	
System (Emergency Light and Switchyard area	
Light)	
Sub-station all Equipment Testing &	
Commissioning including both transformer & all	
Outgoing Feeders	
	termination with properly laying, clamping and labeling incoming all Mechanical & Electrical accessories as approved. Supply and Installation of Sub-station Earthing System (Ground mesh & Copper cladded rod with cad welding) Sub-station Earthing System linked with Mechanical and Electrical Equipments, Control Building surge protection & all other steel accessories like Fence, Main Gate, Barbed Wire etc. Supply and Installation of Sub-station Lighting System (Emergency Light and Switchyard area Light) Sub-station all Equipment Testing & Commissioning including both transformer & all

BANGLADESH	RURAL ELECTRIFI	ICATION BOARD	
ON AND COMM	ISSIONING OF ELE	CTRIC DISTRIBUT	ION SYSTEM.
Revised by	Approved by	Page No.	Revision No
BREB	BREB Board	Page 17 of 25	4
	PBS Instruction ON AND COMM Revised by	PBS Instruction 100-20/ BREB Inst ON AND COMMISSIONING OF ELE Revised by Approved by	

(Md Mozibur Rahman) Consultant TAPP BREE

(Md. Duhidul Islam) Consultant TAPP BRF

(Md. Mozammei Huq) (Md. Abdul Khaleque)

(Md. Ahsanul Haque) Consultant TAPP, BREB

(Debasish Chalaportty) PD, TAPP, BREB

৬২১ তম বোর্ড সভায় অনুমোদিত সিদ্ধান্ত নং ১৭৭০৫

(Kamini Alisan Mollik) Asst. Serv (Ropert) Direct

(g)	Stair Case Railing and Lime Concrete	
(h)	finishing on Roof Top. Plumbing, Electrical Wiring, Switch-Sockets, Fans, Exhaust Fans, Lighting Works of Control Building	7
(i)	Sanitary fitting in Wash Room & Toilets, Building Front Ramp/ Stair Finishing.	
(j)	Control Building Painting Works (Inner, Plastic Paint, and Other Weather Coat)	
(k)	Complaint Room Counter Slab, Plinth Protection Works, Steel Door for Duct Room, Cat Ladder, final paint & Other miscellaneous works.	
(1)	All Foundations of Switchyard and Plinths including provisional equipment foundations.	
(m)	Switchyard final civil works for drainage system with out-let pit, all cable trenches & ducts including cover slab/ duct sealing.	
(n)	Installation of all switchyard supporting structures e.g. CB structure, LA structure, Landing structure including control building all accessories/ components required for fitting & fixing up to commissioning.	
(0)	Site Development/ Earthworks including leveling and brick fill up to FGL.	
(p)	Construction of internal roads (as required), Pump House, Septic Tank, Sock Pit, Approach road, back filling, beautification (e.g. gardening) and all other final finishing works.	
(q)	Construction of RCC retaining wall up to grade beam level.	
(r)	Construction of RCC retaining wall up to FGL level.	
(s)	Completion of Boundary Wall with weather coat paint and barbed wire	

	BANGLADESH	RURAL ELECTRIFI	ICATION BOARD	
	PBS Instructio	n 100-20/ BREB Inst	truction 500-07:	
ENERGIZATI	ON AND COMM	ISSIONING OF ELE	CTRIC DISTRIBUT	ION SYSTEM.
Date of Origin	Revised by	Approved by	Page No.	Revision No
07/03/1979	BREB	BREB Board	Page 18 of 25	4
Revision Date: 31	/04/1995, 14/11/19	996, 01/09/2013 & 1		

(Md. Mozibur Rahman)

(Md. Duhidul Islam) Consultant TAPP BREP (Md. Mazammel Huq) Consultant, TAPP BRE (Md. Abdul Khaleque)
Consultant TAPP RREP

(Md. Ahsanul Haque) Consultant TAPP, HREB

(Debasish Chakrabortty) PD,TAPP, BREB ৬২১ ৩ম বেভি সভায় অনুমোদিত সিদ্ধান্ত নং ১৭৭০০

(Ramful Ansan Molliu)

(t)	Completion of Chain Link fencing and gates as per approved layout.	
(u)	Completion Guard House, Main Gate and Site access road.	
(v)	Sub-station yard surface finishing with 1" - 1.25 " washed stone gravelling of 4" depth.	
(w)	Supply and Installation of Air Conditioning System in Control Room with all accessories and properly laid water drainage pipes (2 tons 4 nos.)	
(x)	Supply and Installation of water pump motor set with all accessories/ components required for fitting & fixing in required depth for drinking water supply including pump house.	
(y)	Supply and Installation of liter (British gallon) overhead water tank including all pipe connection complete as required at site.	
(z)	Supply and Installation of Fire Detection and Protection Facilities in control room building including all accessories.	
(aa)	Installation of Sand Bucket & Fire Extinguishers (Dry Chemical Powder Type 6 Kg) adjacent to Power Transformer (2) + (CO ₂ Type 5 Kg): Control Room (2) & complaint Room	
04	ENVIRONMENTAL (ESMF Related) WORKS	
(a)	Supply of First Aid Box with standard contents.	
(b)	Site cleaning dust control, solid and organic waste management, temporary fencing at construction area, site leveling, dressing etc.	

BUTION SYSTEM.
IBUTION SYSTEM.
Revision No
25 4
of

(Md. Meriour Rahman)

(Md. Duhidul Islam) Consultant, TAPP BREE

(Md. Mozammei Huq) Consultant, TAPP, BRET (Md. Abdul Khaleque)

৬২১ তম বোর্ড সভায় **অনুয়োদিত সিদ্ধান্ত নং** ১৭৭০ ত

(Md. Ahsanul Haque) Consultant, TAPP, BREB (Debasish Chakra/ortty) PD,TAPP, BREB.

(Kamiral Ahsan Mollik)
Asst Secu (Roard)

(c)	25	Provide PPE, Supply drinking water and arrange accommodation with proper sanitation facilities to the labors.	
(d)		Find the depth of ground water level at least two locations of the site to meet the requirement of all parameters for drinking water standard.	э э
05		MISCELLANEOUS	
(a)		Delivery of Furniture for Control Room (Table with side rack: 1, Revolving Chair: 1, Visiting Chair: 4, File Cabinet of three drawer: 1, Computer Table: 1)	2
(b)		Delivery of Desktop Computer including all accessories/	
06		TECHNICAL (O&M) TRAINING SERVICES	
8	2°	Provide 7 days Technical Training for 8 Nos. of BREB/ PBS personnel against each Sub-station on operation, maintenance, protection and control.	
07		OTHERS	
(a)		Site safety Sign & Awareness Notice	
(b)			
(c)			

Accepted	Not Accepte
	Accepted

- 1. Pre-Commissioning performed by (Name & Designation with Seal & Signature):
- 2. Pre-Commissioning Witnessed by the members of Technical Team (Name & Designation with Seal & Signature):

	BANGLADESHI	RURAL ELECTRIFI	CATION BOARD	4
	PBS Instructio	n 100-20/ BREB Inst	truction 500-07:	
ENERGIZATI	ON AND COMMI	SSIONING OF ELE	CTRIC DISTRIBUT	ION SYSTEM.
Date of Origin	Revised by	Approved by	Page No.	Revision No
07/03/1979	BREB	BREB Board	Page 20 of 25	4
Revision Date: 31	/04/1995_14/11/19	996, 01/09/2013 & 1	9/02/2020	

(Md Musitur Rahman) Consultant TAPE BREE

(Md. Ansanul Haque) Consultant, TAPP, HREB (Md. Duhidul Islam) Consoliant, TAPP BREI (Md. Mozammel Huq) Consultant, TAPP BRET (Md. Abdul Khaleque) (Md. Ansanul Haque) Consultant TAPP, BREB Consultant TAPP, BREP

৬২১ তম বোর্ড সভায় অনুমোদিত সিদ্ধান্ত নং ১৭৭০০

(Debasish Chakrabortty) PD,TAPP, BREB.

(Kamiul Ahsan Moint)
Asst. Secy. (Board), BRED

Notes(If any):		
42		
-		
1		4
		1
1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		
60 30		
**		
5		
	= ×	

	BANGLADESH I	RURAL ELECTRIFI	CATION BOARD	
		n 100-20/ BREB Inst		
ENERGIZATI	ON AND COMMI	SSIONING OF ELE	CTRIC DISTRIBUT	ION SYSTEM.
Date of Origin	Revised by	Approved by	Page No.	Revision No
07/03/1979	BREB	BREB Board	Page 21 of 25	4

Revision Date: 31/04/1995, 14/11/19

(Md. Mozibur Rahman) (Md. Duhidul Islam)
Consultant TAPP BREPConsultant, TAPP BREP

(Md. Molammei Hug) Consultant, TAPP, BREI

(Md. Abdul Khaleque)
Consultant TAPP BRER

৬২১ তম বোর্ড সভায় অনুমোদিত সিদ্ধান্ত নং ১৭৭০০

(Md. Ahsanul Haque) Consultant TAPP, HREB

(Debasish Chakrabortty) PD, TAPP, BREB.



(Kamrul Ahsan Mollik) Asst, Secy. (Board), BREB.

DECLARATION

We the undersigned checked the above mentioned works and equipment, verified performance and quality of works and found satisfactory as a part of Testing and Pre-commissioning on today ----- 20---. The indoor type Sub-station is ready for energization and fit for commercial operation.

SL No.	Name	Designation & Office/ Organization	Signature
01			
02			
03	9		
04			
05		4	
06			15 35
07	W E	H L HW	
8			
09			
10	-		
11			
12			
13	= = =		
14			

	BANGLADESH I	RURAL ELECTRIFI	CATION BOARD	*
	PBS Instructio	n 100-20/ BREB Inst	truction 500-07:	
ENERGIZATI	ON AND COMMI	ISSIONING OF ELE	CTRIC DISTRIBUT	ION SYSTEM.
Date of Origin	Revised by	Approved by	Page No.	Revision No.
07/03/1979	BREB	BREB Board	Page 22 of 25	4
Revision Date: 31	/04/1995, 14/11/19	996, 01/09/2013 & 1	9/02/2020	

(Mo. Mozibur Rahman)
Consultant TAPP BREB

wid. Nozammer Huq, Consultant, TAPP, BREB

(Md. Abdul Khaleque) Consultant TAPP, BREB

(Md. Ahsanul Haque) Consultant, TAPP, HREB

PO, TAPP, BREB

(Debasish Chakrabortty) ২১ তম বোর্ড সভায় অনুমোদিত সিদ্ধান্ত নং ১৭৭০০

(Kamrul Ahsan Molhik) Asst. Secy. (Board), BREB.

BREB Form No. 458

REQUEST FOR OUTAGE

		THE CENT OF THE CONTROL OF THE CONTR
	Serial:	Date:
1.	То	AGM(O&M) of PBS
2.		nested for the following line section:
	a) Substation	b) Feeder:
	c) From pole	to pole including all laterals and taps in
	between	these poles.
3. Out	age requested of	n From Hrs to Hrs.
4.	Purpose:	
5. Mr.		Having signature is authorized to receive the
6. Nai	Contractor me & location of	of device by which the line section will be put out of service:
	Substation _	Ckt Village pment: Pole:
7.	Crounds room	ired: 3φ / 1φ
8.		mer affected (approximate)
0.	a) Domestic	b) Industrial c) Agricultural
	Approved by	AGM(O&M)
Clear	ance is hereby	given for re-energization of the above line section with immediate effect.
	Authorized s	ignature Date Time
Сору	to: JE, PBS/ A	E of BREB (if applicable)/ Contractor or requesting person.

	BANGLADESH I	RURAL ELECTRIFI	CATION BOARD	
		n 100-20/ BREB Inst		
ENERGIZATI	ON AND COMMI		CTRIC DISTRIBUT	ION SYSTEM.
Date of Origin	Revised by	Approved by	Page No.	Revision No
07/03/1979	BREB	BREB Board	Page 23 of 25	4
Revision Date: 31	/04/1995, 14/11/19	996, 01/09/2013 & 1	9/02/2020	

(Md Mozibur Rahman)
Consultant TAPP RREP

(Md. Duhidul Islam) Consultant TAPP BREP

(Md. Mdzammei Huq) consultant, TAPP, BREF

(Md. Abdul Khaleque) Consultant, TAPP, BREB

(Debasish Chalkrabortty)
PD, TAPP, BREB

(Kammi Ahsan Mollik) Asst. Secy. (Board), BREB.

(Md. Ahsanul Haque) Consultant TAPP, BRER

BREB Form No. 459

(Page-1 of 2)

Office of the Executive Engineer, BREB

T	-17	~	
ĸ	a:		_

To_

Date:

NOTICE	OF ELF	CTRICAL	SUB-STATION	LINE ENERGIZATION
In contrast to the second second second	The second secon			

AGM (O&M) of _

on		Circuit Group
or	W	ork Order No
line energizati	on Date:	Time:
ions to be ener	gized:	
Pole Number		Remarks
From	То	(Back Bone/ Lateral/ Left Tap/ Right Tap etc.)
8€3		
Α.	74	
Si		
8		20
(6)		
		9
14		
	S	
	or line energizations to be ener Pole N	From To

	BANGLADESH I	RURAL ELECTRIFI	CATION BOARD	
	PBS Instructio	n 100-20/ BREB Inst	ruction 500-07:	
ENERGIZATI	ON AND COMMI	SSIONING OF ELE	CTRIC DISTRIBUT	ION SYSTEM.
Date of Origin	Revised by	Approved by	Page No.	Revision No
07/03/1979	BREB	BREB Board	Page 24 of 25	4
Revision Date: 31	/04/1995, 14/11/19	996, 01/09/2013 & 1	9/02/2020	<u>y</u>

(Ma Mezibur Rahman)

(Md. Alisanul Hague) Consultant, TAPP, BREB

(Md. Mozammer Huy, Consultant, TAPP BRE

(Md. Abdul Khaleque) Consultant, TAPP, BREB

(Md. Duhidul Islam)
(FP Consultant TAPP BRF
(Md. Ahsmul Haque)
Consultant TAPP, BREB

(Debasish Chakrabortty) PD, TAPP, BREB

৬২১ তম বোর্ড সভায় অনুমোদিত সিদ্ধান্ত নং ১৭৭০০

(Kammi Ahsen Molifie) Asst. Secy. (Board), BREB.

BREB Form No. 459

(Page-2 of 2)

(Back page)
Information for installed equipment of constructed electric sub-station/ lines (transformer, re-closer/

SL No.	Sub-Station Name and ID	Name of Equipment	Manufacturer's Serial No	Location or SS Data		KVA/ Amp	Phase of
	No. (For SS Energization)			Pole No./ SS Name	Vill/ Baza/ SS ID	Rating	Instal
	ed that the sub-stat	ion/line section	and equipment sh	own in page	1 & 2 is read	dy for energ	gization
Votifie	ed that the sub-stat			Si	gnature of c		
	ed that the above S	Sub-station/ line	e section is ready f		gnature of c		
Certifi				or energizatio	gnature of co	ontractor	
Certifi	ed that the above S	gineer/RE or PI	BREB LCI/ S	or energization	gnature of con. JE/JE/AGM	ontractor	

	BANGLADESH	RURAL ELECTRIFI	ICATION BOARD	
	PBS Instructio	n 100-20/ BREB Inst	truction 500-07:	
ENERGIZATI	ON AND COMM	ISSIONING OF ELE	CTRIC DISTRIBUT	ION SYSTEM.
Date of Origin	Revised by	Approved by	Page No.	Revision No.
07/03/1979	BREB	BREB Board	Page 25 of 25	4

BREB/ Consultant/ Contractor

Executive Engineer, REB or Sr GM/GM

(Md. Mozibur Rahman) onsultant TAPP BREP (Md. Duhidul Islam) (Md. M. zammei Huq) Consultant TAPP BREF onsultant, TAPP BREP

The Sub-station/ line sections as per above statement is/are taken over.

Copy to:- Sr GM/GM/ AGM(O&M)/ Consultant/Contractor

(Md. Abdul Khalegue)

৬২১ তম বোর্ড সভায় অনুমোদিত সিদ্ধান্ত নং ১৭৭০০

(Md. Ahsanul Haque)
PD, TAPP, BREB.

(Ramful Absan Mollik)
Asst. Secy. (Board), BREB.